Bruhath Benglauru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.

Schedule - B

Name of the Work :Development of roads and drains in ward no. 12 Shettihalli

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted Muniraju B	
				In Figures (Rs)	In Words (Rs)
1	Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specifications and directions of engineer in charge of the work	Cum	1589.04	184.67	Rupees One Hundred and Eighty Four and Sixty Seven Paisa only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 complete as per specifications and directions of engineer in charge of the work	Cum	202.76	5414.39	Rupees Five Thousand Four Hundred and Fourteen and Thirty Nine Paisa Only
3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafairmed -2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings,pedastals,retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	cum	499.16	6687.06	Repees Six Thousand Six Hundred and Eighty Seven and Six Paisa Only

B. Muniraju
Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted **Muniraju B**	
				In Figures (Rs)	In Words (Rs)
4	Providing and removing centering, shuttering, strutting,. propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached1 pilasters, buttresses, plinth cilis and string courses cost of all materials, labour complete as per specifications and directions of engineer in charge of the work	sqm	3934.50	325.95	Rupees Three Hundred and Twenty and Ninety Five Paisa only
5	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and directions of engineer in charge of the work	Tonne	30.61	67423.47	Rupees Sixty Seven Thousand Four Hundred and Twenty Three and Fourty Seven Paisa only
6	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	sqm	1076.70	1763.16	Rupees One Thousand and Seven Hundred and Sixty Three and Sixteen Paisa Only

B. Muniraju

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner